



APPROVED	DATE
DEVELOPMENT CONTROL MANAGER	

- LEGEND**
- ROAD CENTRELINE
 - ▲ 2.5% ROAD CROSSFALL
 - STORMWATER MANHOLE
 - KERB INLET
 - STORMWATER PIPE

- GENERAL NOTES**
1. THE DESIGN ON THIS DRAWING REMAINS THE PROPERTY OF KSS CONSULTING ENGINEERS INC. AND IS SUBJECT TO COPYRIGHT.
 2. THE CONTRACTOR IS TO CONFIRM ALL DIMENSIONS ON SITE AND TO REPORT ANY DISCREPANCIES TO THE ENGINEER IMMEDIATELY.
 3. ALL WORK IS TO BE EXECUTED IN ACCORDANCE WITH THE PROVISIONS OF SANS 1040.
 4. NOTE THAT NO OTHER BARRIERS SERVICES ARE INDICATED ON THIS DRAWING.
 5. CONSTRUCTION ARE NOT TO BE SCALED FROM THIS DRAWING.
 6. THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION UNLESS SPECIFICALLY DIRECTED BY THE ENGINEER.
 7. THE CONTRACTOR IS REQUIRED TO MINIMISE DUST AND NOISE NUISANCE TO ALL SURROUNDING PROPERTIES.
 8. A MINIMUM NOTICE PERIOD OF 24 HOURS IS REQUIRED FOR ANY INSPECTION.
 9. CONSTRUCTION IS TO PROVIDE A DETAILED SCHEDULE OF INFORMATION REQUIRED INDICATING ALL SUCH DATES.

- CIVIL NOTES**
1. ALL WORK IS TO BE IN ACCORDANCE WITH THE RELEVANT CLASSES OF SANS 1040.
 2. ALL WORK IS TO BE TO DEGREE OF ACCURACY 1:1 UNLESS OTHERWISE SHOWN.
 3. ALL TESTING IS TO BE IN ACCORDANCE WITH CLAUSE 7 OF THE RELEVANT CODE UNLESS REPLACED BY A MUNICIPAL TESTING REQUIREMENT.
 4. THE CONTRACTOR IS TO PROTECT EXISTING ROADWAY STRUCTURES AND BARRIERS SERVICES.
 5. SAMPLES OF FINE BEDDING MATERIAL ARE TO BE APPROVED BY THE ENGINEER PRIOR TO COMMENCEMENT OF ANY PIPE LAYING.
 6. INSPECTION SITES TO BE ESTABLISHED BY AN INDEPENDENT ENGINEERING SUPERVISOR AND THE POSITIONS THEREOF FORWARDED TO KSS CONSULTING ENGINEERS PRIOR TO COMMENCEMENT OF ROAD CONSTRUCTION.
 7. ALL MANHOLE DEPTHS FROM FINISH TO BE TO THE SAME SPECIFICATION AS INDICATED ON THE DRAWING.
 8. ALL MANHOLE DEPTHS ARE TO BE ESTABLISHED BY AN INDEPENDENT ENGINEERING SUPERVISOR AND THE POSITIONS THEREOF FORWARDED TO KSS CONSULTING ENGINEERS PRIOR TO COMMENCEMENT OF ROAD CONSTRUCTION.
 9. THE IN LEVELS ARE TO BE CONFIRMED PRIOR TO CONSTRUCTION.
 10. ALL SW PIPES UNDER ROADWAY TO BE CLASS 1000.

AS-BUILT DRAWING
AND FINAL INSPECTION BY

PRINT NAME	SIGNATURE
PRINT PROF. REG. NO. 1	DATE
A. 26/06/2006 INFORMATION "AS-BUILT"	
NO.	DATE
REVISION	



KSS CONSULTING ENGINEERS INCORPORATED
BUILDING 5, 299 PENDERG, BLACKHEATH, JOHANNESBURG
P.O. BOX 4427, CRESTA, 2118
TEL: (011) 678 9838; FAX: (011) 678 7115
EMAIL: kss@kssinc.co.za

APPROVED

PROJECT
TJGERVALLEI EXT. 1 - 8
REMAINDER OF THE FARM
TWEEFONTEIN No. 372 - J.R.

DESCRIPTION
ROADS & STORMWATER LAYOUT

DESIGNED	PKS	SCALE	1 : 750
DRAWN	AM	DATE	JUNE 2006
CHECKED	PKS	CONTRACT NO
DRAWING NO.	255/01-20		
REVISION	A		

