



APPROVED

DEVELOPMENT CONTROL MANAGER	DATE
-----------------------------	------

- LEGEND**
- 2 x 110mm "KABELFLEX" TELKOM DUCTS
  - 4 x 110mm "KABELFLEX" TELKOM DUCTS
  - 1 x 110mm "KABELFLEX" TELKOM ERP CONNECTION

- GENERAL NOTES**
1. THE DESIGN ON THIS DRAWING REMAINS THE PROPERTY OF KSS CONSULTING ENGINEERS INC. AND IS SUBJECT TO COPYRIGHT.
  2. THE CONTRACTOR IS TO CONFIRM ALL DIMENSIONS ON SITE AND TO REPORT ANY DISCREPANCIES TO THE ENGINEER IMMEDIATELY.
  3. ALL WORK IS TO BE EXECUTED IN ACCORDANCE WITH THE PROVISIONS OF SAWS 100.
  4. NOTE THAT NO OTHER BARRIERS SERVICES ARE INDICATED ON THIS DRAWING.
  5. DIMENSIONS ARE NOT TO BE SCALED FROM THIS DRAWING.
  6. THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION UNLESS SPECIFICALLY REFERENCED AS INDICATED.
  7. THE CONTRACTOR IS REQUIRED TO MINIMISE DUST AND NOISE NUISANCE TO ALL SURROUNDING PROPERTIES.
  8. A MINIMUM NOTICE PERIOD OF 24 HOURS IS REQUIRED FOR ANY INSPECTION.
  9. CONTRACTOR IS TO PROVIDE A DETAILED SCHEDULE OF INFORMATION REQUIRED INDICATING ALL SUCH DATES.

- CIVIL NOTES**
1. ALL WORK IS TO BE IN ACCORDANCE WITH THE RELEVANT CLASSES OF SAWS 100.
  2. ALL WORK IS TO BE TO STANDARDS OF ACCURACY 1:1 UNLESS OTHERWISE SHOWN.
  3. ALL TESTING IS TO BE IN ACCORDANCE WITH CLAUSE 7 OF THE RELEVANT CODE AND TO BE REPLACED BY A MANUFACTURER'S TESTING REQUIREMENTS.
  4. THE CONTRACTOR IS TO PROTECT EXISTING BOUNDARY STRUCTURES AND BARRIERS SERVICES.
  5. SAMPLES OF PIPE BEDDING MATERIAL ARE TO BE APPROVED BY THE ENGINEER PRIOR TO COMMENCEMENT OF ANY PIPE LAYING.
  6. INSPECTIONS SUBJECT TO THE AVAILABILITY OF MUNICIPAL REPRESENTATIVES.
  7. ALL BODIFILL AROUND MANHOLES IS TO BE TO THE SAME SPECIFICATION AS BODIFILL TO THE PIPE.
  8. TWO BENCH MARKS ARE TO BE ESTABLISHED BY AN INDEPENDENT ENGINEERING SURVEYOR AND THE POSITIONS THEREOF FORWARDED TO KSS CONSULTING ENGINEERS PRIOR TO COMMENCEMENT OF ROAD CONSTRUCTION.
  9. ALL LEVELS ARE TO BE CONFIRMED PRIOR TO CONSTRUCTION.
  10. ALL 500mm PIPES UNDER ROADWAY TO BE CLASS 1000.

AS-BUILT DRAWING AND FINAL INSPECTION BY

PRINT NAME	SIGNATURE
PRINT PROF. REG. NO. 1	DATE

A.	26/06/2006	INFORMATION 'AS-BUILT'
NO.	DATE	REVISION

**KSS CONSULTING ENGINEERS INCORPORATED**  
 BUILDING 5, 299 PENDING, BLACKHEATH, JOHANNESBURG  
 P.O. BOX 4427, CRESTA, 2118  
 TEL: 10111 678 9836; FAX: 10111 678 7115  
 EMAIL: kss@kssinc.co.za

APPROVED

PROJECT  
 TIJGERVALLEI EXT. 1 - 8  
 REMAINDER OF THE FARM  
 TWEEFONTEIN No. 372 - J.R.

DESCRIPTION  
 TELKOM LAYOUT

DESIGNED	PKS	SCALE	1 : 750
DRAWN	AM	DATE	JUNE 2006
CHECKED	PKS	CONTRACT NO	.....
DRAWING NO.	255/05-20		
REVISION	A		